

PROGRAM OVERVIEW

GoPort is a program of projects to improve truck and rail access to the Port of Oakland, one of the nation's most vital seaports. It consists of the following components:

- 7th Street Grade Separation West (7SGSW):** Realign and grade separate the intersection near 7th Street and Maritime Street in the heart of the seaport, and construct a rail connection underneath to improve intermodal access and minimize conflicts between rail, vehicles, pedestrians, and bicyclists.
- 7th Street Grade Separation East (7SGSE):** Replace existing railroad underpass between I-880 and Maritime Street to increase clearance for trucks and improve the current shared pedestrian/bicycle pathway.
- Freight Intelligent Transportation System (FITS):** A suite of demonstration information technology projects along West Grand Avenue, Maritime Street, 7th Street, and Middle Harbor Road, that are intended to improve truck traffic flows, increase the efficiency of goods movement operations, and enhance the safety and incident response capabilities throughout the seaport.



PROGRAM NEED

- The Port of Oakland (Port) is one of the top 10 busiest container ports in the U.S., handling 99% of regional containerized goods in Northern California.
- The Port has capacity to support increased freight demands, but severe landside access inefficiencies constrain growth potential.
- Significant traffic congestion occurs within the Port, particularly along Maritime Street, 7th Street, and Middle Harbor Road, due to substantial gate down time required for train crossings at major intersections. Truck queues can take more than one hour and 45 minutes to clear.
- Lengthy queues on the streets with as many as 50 trucks have wait times of up to three hours to enter into marine terminals.
- Idling trucks in long queues cause growing local and regional concerns regarding air quality and greenhouse gas emissions.
- There is limited multimodal access to commercial developments and recreational facilities adjacent to the San Francisco Bay.

PROGRAM BENEFITS

- Congestion relief:** Upgrade technology and infrastructure to minimize and manage truck wait times, manage truck congestion, and improve traffic circulation
- Efficiency:** Improve Port and Rail Yard efficiencies, intermodal yard connectivity, and expand near-dock use of rail and intermodal facilities
- Sustainability:** Reconstruct Bay Trail segment on 7th Street and Maritime Street and reduce emissions/carbon footprint
- Economic stimulation:** Reduce shipping costs, improve Port competitiveness and create jobs



Maritime Street at-grade rail crossing south of 7th Street, March 2016.



Aerial view of the Port of Oakland, March 2016.

STATUS

Implementing Agency: Alameda CTC

Current Phase: Final Design/Construction

- ~\$53 million has been allocated from the Measure BB funds for the environmental and final design phases of the program.
- The City of Oakland was the California Environmental Quality Act (CEQA) lead agency and the Port was the responsible agency for the 2002 Oakland Army Base (OAB) Redevelopment Environmental Impact Report (EIR) and its subsequent 2012 Initial Study Addendum, in which the GoPort Program was included. The Categorical Exclusions (CE) as part of the National Environmental Policy Act (NEPA) clearance were completed for the FITS, 7SGSE and 7SGSW projects in August 2018, October 2018 and March 2019, respectively.

PARTNERS AND STAKEHOLDERS

City of Oakland, Port of Oakland, California Department of Transportation, Union Pacific Railroad, BNSF Railway, San Francisco Bay Area Rapid Transit, Metropolitan Transportation Commission and several utility entities

COST ESTIMATE BY PHASE (\$ X 1,000)

PE/Environmental	\$12,500
Final Design (PS&E)	\$41,700
Right-of-Way	\$89,500
Construction	\$478,300
Total Expenditures Estimate	\$622,000

FUNDING SOURCES (\$ X 1,000)

Measure BB	\$53,020
Federal	\$11,544
State (Senate Bill 1 (SB 1) LPP) ¹	\$7,980
State (SB 1 TCEP) ²	\$187,456
TBD	\$362,000
Total Revenues To Date	\$622,000

¹ Local Partnership Program.

² Trade Corridor Enhancement Program.

SCHEDULE BY PHASE

	Begin	End
PE/Environmental	Fall 2016	2018
CEQA Clearance	-	2012
NEPA Clearance	Fall 2017	Spring 2019
Final Design	Fall 2018	Early 2020
Construction	Spring 2020 ^{3/4}	Late 2023 ⁴

³ Construction related to FITS will begin in fall 2019.

⁴ Construction related to 7SGSW is to be determined.

Note: Information on this fact sheet is subject to periodic updates.